


Cross Sections of Consentable Activities




Pipe Culvert (including extension and removal of) Consent Required under Section 23 (1)(b).



Oversized Box Culvert (including extension and removal of) Consent Required under Section 23 (1)(b).



Trash Screens - Consent Required as it is an alteration to a culvert and has the potential to obstruct flow under Section 23 (1)(c).



Bank Protection Works - Consent not required under LDA 91, (Temporary works may require consent).



Pipe Crossing (in channel) - Consent Required under Section 23 1(a) if placed on bed and under Section 23 (1)(b) if above bed.




Pipe Crossing (above bank) - Consent not required under LDA 91 as it does not affect the watercourse.



Pipe Crossing (below bed) - Consent not required under LDA 91 as it does not affect the watercourse – Potential temporary works consent.




Protruding Pipe Outfall - Consent not required under LDA 91 as it will not act like a dam/weir or like obstruction.



Weir, dam, impoundment or temporary works that obstruct flow - Consent Required under Section 23 1(a).




Bridge (where soffit level is below bank top level) - Consent Required under Section 23 1(b) as it acts like a culvert.



Bridge (where soffit level is below bank top level) - Consent Required under Section 23 1(b) as it acts like a culvert.



Bridge (abutments not reducing flow area/width) - Consent not required under LDA 91 as does not interfere with flow.



Bridge (Abutments restricting flow) - Consent Required under Section 23 1(b) as it acts like a culvert.



Clear span bridge – Consent not required as it does not affect the watercourse.