



**NOTES**

1. Panels to be steel construction. Finish to be erected in accordance with recommendation of the manufacturer.
2. Infill to be vertical bars (number of infill bars to be determined by the manufacturer).
3. Frame to be hot rolled steel hollow section.
4. All safety measures are to be taken with regard to breaking out and mechanical means are to be used where possible. If breaking-out guns are used, the use of anti-vibration gloves and rotation of labour is recommended.
5. Concrete foundation to be ST2 mix.
6. Footway Surfacing to be to footway specification.



Growth, Highways & Infrastructure  
 Suffolk County Council  
 Endeavour House  
 8 Russell Road  
 Ipswich  
 Suffolk IP1 2BX

**DRAWING TITLE**  
 PERMANENT FENCING  
 STANDARD PEDESTRIAN GUARDRAIL

REV.	DESCRIPTION	CHECKED	DATE

INIT.	DATE	PROJECT TITLE	
ORIGINATOR	RY 08/2024	STANDARD CONSTRUCTION DETAILS	
CHECKER	SH 08/2024	SCALE	DATE
DESIGNER	RY 08/2024	N.T.S.	AUG. 2024
REVIEWER	TK 08/2024	DRAWING No. DM-300-04	