



NOTES

1. Paving adjacent to tree pit to be bedded on mortar.
2. Pit to be 1200 x 1200mm, to a minimum depth of 800mm.
3. Base of tree pit to be broken to a depth of 150mm.
4. Tree root ball to be anchored using rootball anchoring system.
5. Root barrier system to be laid to a minimum depth of 1m, or the depth of the deepest known service run (whichever is deepest). Barrier to be installed on pit sides adjacent to service runs only, with a 300mm return at each open corner.
6. Well compacted sub-grade.
7. Perforated PVC watering pipe to be 'Root Rain Precinct' or equivalent approved, coated around rootball. All to manufacturer's instructions.
8. Geotextile fabric laid as blinding below gravel. To be pegged down with metal hoops.
9. Tree pit to be back filled with excavated topsoil.
10. Integral uplighting unit within tree grille, type to be agreed.



Growth, Highways & Infrastructure
 Suffolk County Council
 Endeavour House
 8 Russell Road
 Ipswich
 Suffolk IP1 2BX

DRAWING TITLE
 LANDSCAPE AND ECOLOGY
 TREE PIT DETAIL

REV.	DESCRIPTION	CHECKED	DATE

INIT.	DATE	PROJECT TITLE	
ORIGINATOR	RY 08/2024	STANDARD CONSTRUCTION DETAILS	
CHECKER	SH 08/2024	SCALE	DATE
DESIGNER	RY 08/2024	N.T.S.	AUG. 2024
REVIEWER	TK 08/2024	DRAWING No. DM-3000-01	